MISCELLANEOUS DEPARTMENTS.

GOVERNMENT OF MYSORE—ELECTRICAL DEPARTMENT.

OFFICE OF THE SUPERINTENDING ENGINEER, ELECTRICAL DEPARTMENT, BANGALORE.

Notification dated 7th December 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer Electrical Department, Bangalore, up to 2 P.M. on the 4th January 1939, for constructing Station and Staff quarters at Chitaldrug Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of June 1939.

2. The plans, detailed estimates and conditions may be seen at the Office of the Superintending Engineer, Electrical Department, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,250 cash or Government promissory notes, as earnest money, and be superscribed " Tender for constructing Electrical Biuldings at Chitaldrug Town " in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Superintending Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on the rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than ten per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rates, will not be accepted.

13. Charges on account of water, scaffolding, materials, implements for setting out, barricading, clearing site, supply of workmen, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

Abstract estimate for constructing a combined building for Station, Office and Stores, Chitaldrug Town.

Serial No.	Description of work	Unit	Quantity	Rates to be quoted
1	Earthwork excavation and filling in basement, including watering, ramming, etc.	C.yd.	67	
2	Stone jelly concrete in lime mortar	,,	592	
3	Size stone in lime mortar foundation and basement with bond stones	C.ft.	1,262	
4	Burnt brick in lime mortar superstructure	,,	2,146	
5	Stone slabs 6″ thick, exposed parts dressed and fixed complete	S.ft.	150	
6	Stone slabs 6″ thick, roughly dressed and set in lime ..	,,	155	
7	Chunam plastering, ½″ thick	Sqr.	43.00	
8	Cement pointing with thread lines	,,	2.50	
9	White adn colour-washing, two coats	,,	45.50	
10	Flooring with cement concrete 1½″ thick over 4″ thick lime concrete with ½″ thick cement, plastered and coloured red.	,,	9.59	
11	Burnt brick in lime for pillars 1⅛′×1⅛′ with base and capitals as per design with bond stones at intervals 3 to 4 ft. with lime plastering, whitewashing, etc., complete	No.	6	
12	Terrace filled inwith brick in surki mortar with wedgeshaped R. C. joists with 3″ to 6″ thick surki concrete, 2 courses of flat tiles and surface and ceiling lime plastered, ½″ thick, etc., complete, as per detailed sketch	Sqr.	14.73	
13	Parapet wall built of brick in chunam and lime plastered 9″×1′—9″ with necessary pillasters complete as per design ..	R.ft.	201	
14	Rolled steel girder hoisted and fixed complete, including painting, (Tata's tested)	Cwt.	26.28	

Serial No.	Description of work	Unit	Quantity	Rates to be quoted
15	Teak-wood doors panelled 1¼″ with fixtures, etc., complete as per drawing	S.ft.	126	
16	Teak-wood windows glazed 1¼″ thick shutters frames 3″×4″ with ¾″ dia. iron-bars with fixtures, complete as per drawing.	S.ft.	123	
17	Teak-wood ventilators, glazed 1″ thick shutters frames 3″×3″ with iron bars ¾″ dia., complete	,,	68	
18	R. C. jelly work fixed complete, as per design	,,	125	
19	T. W. Partition ¾″ thick planks with tongue and groove joints with fittings complete including 2 coats of wood-oiling as per drawing	S.ft.	225	
20	Boxing girders with brick in cement and lime plastering complete with necessary wire-netting for binding	R.ft.	45	
21	Providing and fixing 3″ square size rain water down pipes, made of No. 22 B. W. G. plain galvd. iron-sheeting, complete, including painting	R.ft.	60	
22	Silicate painting, 2 coats	Sqr.	4.43	
23	Providing and fixing 2″ G. I. pipe for flag-staff and painting	L. S.		
24	Cement concrete with centering, including plastering at sides and bottom	C.ft.	36	
25	Printing letters 6″×4″ for the name of the building on the parapet wall with cement and painted, complete	L. S.		
26	Providing and fixing slabs 4″ thick on 3″ lime concrete, below rain water pipes, 2″×2′	S.ft.	40	

Abstract estiamte for constructing a Senior Operator's Quarters at Chitaldrug Town.

1	Earthwork excavation in ordinary soil and filling in basement including watering and ramming	C.yd.	65	
2	Stone jelly in lime mortar foundation	C.ft.	513	
3	Stone in clay foundation and basement with bond stones	,,	1,664	
4	Burnt brick in clay superstructure	,,	1,794	
5	Burnt brick in mortar superstructure	,,	912	
6	Stone slabs 6″ thick and fixed in lime mortar	S.ft.	202	
7	Stone slabs 3″ thick fixed in lime mortar	,,	28	
8	Pointing with cement mortar, with thread lines	Sqr.	2.34	
9	Plastering with mortar	,,	55.61	
10	White and colour washing, 2 coats	,,	57.95	
11	Plain cornice, 9″ deep	R.ft.	103	
12	Burnt brick in mortar parapet walls 9″ thick and 1½ ft. to 2 ft. high complete	,,	100	
13	Flooring with 1½″ cement concrete on a bed of 3″ lime mortar concrete and ½″ thick cement plaster	Sqr.	10.07	
14	Roofing with first class Mangalore Tiles on T. W. reepers 2″×1″ including wood-oiling to reepers	,,	11.56	
15	Ridge tiles set in mortar and cement pointed	R.ft.	73	
16	Brick nogged terrace filled in with brick in surki mortar complete with wedge R. C. joists with surki concrete, 2 coats of flat tiles, surface and ceiling plastered as per sketch	Sqr.	5.44	
17	Teak-wood work with wood-oiling, etc., complete	C.ft.	60.11	
18	Plain teak wood cave-board 9″×¾″ fixed complete	R.ft.	162	
19	Doors with teak wood frames and honney-wood battened shutters 1″ thick including fixtures, complete	S.ft.	183	
20	Windows with teak-wood frames and honney-wood battened shutters with iron bars, etc., ⅝″ dia. with fixtures	,,	110	
21	Teak wood cup-boards with battened shutters, 1″ thick and T. W. planks for shelves	S.ft.	48	
22	Steel girders fixed complete including painting (Tata's tested)	Cwt.	4.83	
23	Expanded metal 3″×1½″ with ⅛″ strands with T. W. frames work fixed complete with doors	S.ft.	111	
24	Chocolate painting two coats	Sqr.	11.84	
25	Ventilating tiles fixed with cement	No.	6	
26	Constructing sinks 3′×3′ complete	,,	2	
27	Stone mortar and pestle, fixed complete	,,	1	
28	Rain water down pipes 3″ dia. of plain G. I. sheeting fixed with clamps, etc., complete, including painting	R.ft.	50	
29	Constructing chimney, etc., in kitchen	L. S.	..	
30	Levelling the ground	L. S.	..	

Abstract estimate for constructing one unit of double block of Operators' Quarters at Chitaldrug Town :—

Sl. No.	Description of work	Unit	Quantity	Rates to be quoted
1	Earthwork excavation and filling in basement including watering and ramming	C.yd.	74	
2	Stone jelly in lime mortar, concrete	C.ft.	702	
3	Size stone in clay, foundation and basement with bond stones	,,	1,762	
4	Burnt brick in clay, superstructure	,,	3,338	
5	Burnt brick in lime mortar superstructure	,,	859	
6	Stone slabs 6″ thick roughly dressed and fixed in lime	S.ft.	278	
7	Cement pointing with thread lines	Sqr.	3·12	
8	Chunam plastering, 2 coats	,,	80·00	
9	White and colour washing 2 coats	,,	83·00	
10	Plain cornice 9″ thick as per design	R.ft.	73	
11	Burnt brick in lime mortar wall 9″ thick as per design	,,	70	
12	Flooring with 1″ thick cement concrete over 3″ lime concrete with ½″ cement plaster on top	Sqr.	13·16	
13	Roofing with 1st class Mangalore Tiles on T. W. reepers 2″×1″ including wood oiling to reepers	,,	20·31	
14	Ridge tiles set in mortar and cement pointed	R.ft.	126	
15	Brick nogged terrace filled in with wedgeshaped R.C. joists with surki concrete, 2 coats of flat tiles, surface and ceiling plastered	Sqr.	5·44	
16	Plain T. W. eaveboard 9″×¾″ fixed complete	R.ft.	192	
17	Teakwood wrought and put up with wood oiling 2 coats	C.ft.	98·34	
18	Teakwood doors with battened shutters 1″ thick with fixtures, etc., complete as per design drawing	S.ft.	241	
19	Teakwood windows with battened shutters and iron bars and necessary fixtures, etc., complete as per drawing	,,	188	
20	Teakwood cupboards with panelled shutters and T. W. planks for shelves	,,	96	
21	Expanded metal 3″×1½″ mesh with ⅛″ strands with T. W. frame work with doorways, etc., complete	,,	119	
22	Chocolate painting 2 coats	Sqr.	14·57	
23	Ventilating tiles	No.	8	
24	Constructing sinks, complete with outlet pipes	,,	2	
25	Providing and fixing stone mortar and pestle	,,	2	
26	Chunam borders at the ends of roof	R.ft.	22	
27	Rain water down pipes 3″ dia. of plain galvanized iron sheet fixed with clamps, etc., complete including painting	,,	65	
28	Constructing chimney, etc., in kitchen	No.	2	
29	Rolled steel girders (Tata's tested) fixed complete including painting	Cwt.	4·34	
30	Providing and fixing copper handas in bath-room	No.	2	
31	Levelling ground	..	..	

Abstract of the estimate for constructing Linemen's Quarters at Chitaldrug Town :—

1	Earthwork excavation and filling in basement including watering and ramming	C.yd.	40	
2	Stone jelly in lime mortar concrete for foundation	C.ft.	353	
3	Size stone in clay foundation and basement with bond stones	,,	1,195	
4	Burnt brick in clay, superstructure	,,	2,138	
5	Burnt brick in lime mortar superstructure	,,	433	
6	Stone slabs 6″ thick roughly dressed and set in lime	S.ft.	144	
7	Binding wall 6″×6″ of brick in lime and chunam plastered	R.ft.	·28	
8	Chunam plastering, two coats	Sqr.	52·87	
9	Pointing with cement mortar with thread lines	,,	1·70	
10	White and colour washing, two coats	,,	54·57	
11	Roofing with first class Mangalore Tiles on T. W. reepers including wood oiling to reepers	,,	16·41	
12	Ridge tiles set in mortar and cement pointed	R.ft.	80	
13	Ventilating tiles set in mortar and cement pointed	No.	20	
14	T. W. wrought and put up with 2 coats of wood oiling	C.ft.	53·07	
15	Doors with teakwood frames and Honnewood battened shutters 1″ thick with fittings, etc., complete	S.ft.	195	
16	Windows with T. W. frames and Honnewood battened shutters 1″ with iron bars ⅝″ dia. and fittings, etc., complete	,,	90	

Sl. No.	Description of work	Unit	Quantity	Rate to be quoted
17	Chocolate painting, two coats	Sqr.	6·00	
18	Constructing sinks in the bath rooms	No.	5	
19	Providing stone mortar and pestle	No.	5	
20	Flooring with 3″ lime concrete and 1″ cement concrete with ½″ thick cement plastering on top	Sqr.	9·44	
21	Constructing parapet wall with brick in lime mortar 2′ high with Cuddapah slab on top with plastering, etc., complete.	R.ft.	44	
22	Providing expanded metal trellis work in front verandah including a door in each	S.ft.	300	
23	Levelling ground	L.S.	..	

Abstract estimate for constructing the Latrine.

1	Earthwork excavation for foundation and filling in basement ..	C.yd.	4	
2	Stone in clay foundation and basement	C.ft.	130	
3	Burnt brick in lime mortar	,,	196	
4	Chunam plastering, two coats	Sqr.	4·91	
5	Cement pointing with thread lines	,,	0·56	
6	White and colour washing, two coats	,,	5·47	
7	Cement plastering, ½″ thick	,,	0·79	
8	Tar-washing, 2 coats	,,	0·63	
9	Flooring with 1″ cement concrete and ½″ cement plaster over a bed of 3″ lime concrete	,,	0·38	
10	Fixing outlets and constructing drains	L.S.	..	
11	Providing galvanised iron sheet tubs 12″×6″ of 22—B.W.G. complete with tarring	No.	6	

Notification dated 8th December 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, Bangalore, up to 2 P.M. on the 3rd January 1939. For constructing 1¾ blocks of four Linemen's Quarters at Sonnur Village, Malur Taluk, on the Sarjapur Kolar Gold Fields Transmission Line. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of March 1939.

2. The plans, detailed estimate and conditions may be seen at the Office of the Superintending Engineer, Electrical Department, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 (Two hundred and fifty only) in cash of Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Linemen's Quarters at Sonnur, Malur Taluk", in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within eight (8) days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money forefeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all the matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Charges on account of water, scaffolding materials, implements for setting out, barricading clearing site, supply of work, etc., that may be found necessary during the execution will not be paid for separately but should be borne by the contractor.

Abstract of the estimate for constructing Linemen's Quarters at Sonnur, Malur Taluk.

Item No.	Description of work	Unit	Quantity	Rates to be quoted
				Rs. a. p.
1	Earthwork excavation and filling in basement including watering and ramming	C.yd.	33	
2	Stone jelly in lime mortar concrete for foundation	C.ft.	287	
3	Size stone in clay foundation and basement with bond stones	,,	911	
4	Burnt brick in clay superstructure	,,	1,692	
5	Burnt brick in lime mortar superstructure	,,	513	
6	Stone slabs 6" thick roughly dressed and set in lime	S.ft.	195	
7	Binding wall 6"×6" of brick in lime mortar and chunam plastered	R.ft.	28	
8	Chunam plastering, two coats	Sqr.	45·04	
9	Pointing with cement mortar with thread lines	,,	1·45	
10	White and colour washing, two coats	,,	46·49	
11	Roofing with first class Mangalore tiles on T.W. reepers including wood oiling to reepers	,,	14·43	
12	Ridge tiles set in mortar and cement pointed	R.ft.	77	
13	Ventilating tiles set in mortar and cement pointed	No.	16	
14	T.W. wrought and put up with two coats of wood oiling	C.ft.	52·48	
15	T.W. doors with battened shutters 1" thick fittings, etc., complete as per drawing	S.ft.	156	
16	T.W. windows with battened shutters 1" thick iron bars $\frac{5}{8}$" dia. and fittings, etc., complete as per drawing	,,	60	
17	Chocolate painting, two coats	Sqr.	4·62	
18	Constructing sinks in bath rooms	No.	4	
19	Providing stone mortar and pestle	,,	4	
20	Flooring with 3" lime concrete and 1" cement concrete with $\frac{1}{2}$" thick cement plastering on top	Sqr.	7·58	
21	Constructing parapet wall with brick in lime mortar 2" high with Cudappah slabs on top with plastering, etc., complete.	R.ft.	37	
22	Providing expanded metal trellis work with T.W. frames in front verandah including a door in each as per design	S.ft.	241	
23	Levelling the ground	L. S.		

N.B.—The details given are for one block of four rooms only.

Notification dated 8th December 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, Bangalore, up to 2 P.M. on the 3rd January 1939, for constructing Linemen Quarters at Harchalli and Honaganahalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of February 1939.

2. The plans, detailed estimate and conditions may be seen at the Office of the Superintending Engineer, Electrical Department, Bangalore, between the hours 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 for buildings at Harohally and Rs. 100 for buildings at Honaganahally in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Electrical Quarters at Harohally and Honaganahally" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on the rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specially provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific terms of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Charges on account of water, scaffolding materials, implements for setting out, barricading, clearing site, supply of work, etc., that may be found necessary during execution, will not be paid for separately, but should be borne by the contractor.

Abstract of the estimate for constructing Linemen's Quarters at Harohally and Honaganahally.

Item No.	Description of the work	Unit	Quantity	Rates to be quoted
				Rs. a. p.
1	Earthwork excavation and filling in basement	C.yd.	16	
2	Concrete stone jelly in lime mortar foundation	C.ft.	176	
3	Stone in clay foundation and basement including bond stones, as per specifications	,,	414	
4	Burnt brick in clay superstructure	,,	853	
5	Burnt brick in mortar superstructure	,,	332	
6	Burnt stone slabs 4″ to 6″ thick roughly dressed and fixed in mortar	S.ft.	70	
7	Chunam plastering, two coats	Sqr.	24	
8	Cement pointing with thread lines	,,	1	
9	White and colour washing, two coats	,,	·25	
10	Roofing with first class Mangalore tiles on teakwood reepers 2″×1″ including, wood oiling, two coats to reepers ..	,,	9·16	
11	Ridge tiles set in mortar and cement pointed	R.ft.	25	
12	Ventilating tiles, set in cement mortar	No.	8	
13	Teakwood wrought and put up with two coats of wood oiling.	C.ft.	38·27	
14	Teakwood battened doors with 1″ thick shutters and all fixtures complete, as per drawing	S.ft.	78	
15	Teakwood battened windows with 1″ thick shutters $\frac{5}{8}$″ dia. iron bars all fixtures, etc., complete as per drawing	,,	45	
16	Teakwood shelves with battened shutters, planks, frame 3″×1″, etc.	,,	30	
17	Chocolate painting, two coats	Sqr.	4	
18	Constructing sinks	No.	2	
19	Providing stone mortar and pestle	,,	2	
20	Flooring with $1\frac{1}{2}$″ cement concrete on 3″ lime concrete and $\frac{1}{2}$″ thick cement plaster on top	Sqr.	4	
21	Levelling the ground	L. S.		
22	Chunam borders 6″×3″ at the end of the roof	R.ft.	32	

L. A. H. WINCKLER,
Superintending Engineer.

GOVERNMENT HIGH SCHOOL, CHIKMAGALUR.

Notification No. 1 *dated* 13*th December* 1938.

The following articles of the Government High School Hostel, Chikmagalur, will be sold by public auction in the High School premises on Friday the 23rd December 1938 at 4 P.M.

Terms and conditions of auction will be as follows :—

(1) The article will be knocked down to the highest bidder.

(2) The sale amount should be paid immediately. In case it could not be paid immediately, a deposit of 25 per cent of the amount will be recovered from the successful bidder immediately the articles are knocked down in his favour and such deposits shall be forfeited to Government in case of any default to pay the full purchase money within 24 hours of sale.

(3) Cash should be paid in full for articles purchased by bidders before delivery and the articles will not be allowed to be removed from the place of auction, until after the close of the sale.

(4) In case of default of payment of the whole or any portion of the purchase amount by the bidder, the articles will be resold and the bidder will be liable to any loss incurred thereby.

(5) All articles purchased will be at the risk of the purchaser thereof from the time of sale.

(6) The successful bidder must remove the articles within 24 hours after his bid has been accepted.

(7) The decision of the Officer who conducts the auction will be final in all matters pertaining to the auction.